BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT34167

Park Development and walking Track in Thirumenahalli Lake at Ward No.05 Jakkur

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
1	7.04	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.	Cum	344.07	Rupees Three Hundred Forty Four And Paise Seven Only
2	2.31	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @ 0.465cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5976.92	Rupees Five Thousand Nine Hundred Seventy Six And Paise Ninety Two Only
3	15.40	Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Cum	1107.01	Rupees One Thousand One Hundred Seven And Paise One Only
4	18.88	Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	6239.29	Rupees Six Thousand Two Hundred Thirty Nine And Paise Twenty Nine Only
5	17.60	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	281.93	Rupees Two Hundred Eighty One And Paise Ninety Three Only
6	45.60	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.	Sqm	92.06	Rupees Ninety Two And Paise Six Only
7	2472.00	Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqm	70.19	Rupees Seventy And Paise Nineteen Only
8	1920.00	Construction of embankment with approved material Gravel/Murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications, including cost of gravel / murrum, watering charges & compaction by vibratory roller to 95% of modified proctors density.	Cum	373.99	Rupees Three Hundred Seventy Three And Paise Ninety Nine Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	ntity	Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
	6000.00	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees of girth upto 300mm, by manual means, in area of light jungle, removal of stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	Sqm	11.51	Rupees Eleven And Paise Fifty One Only
10	156.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge.	Nos	469.50	Rupees Four Hundred Sixty Nine And Paise Fifty Only
11	90.00	Sand filling in wells complete as per drawing and technical specifications including cost of all materials, labour, HOM, form works, scaffolding & centering complete as per specifications.	Sqm	3172.58	Rupees Three Thousand One Hundred Seventy Two And Paise
12	900.00	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778 having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings, this includes jointing of pipes and fittings with one step solvent cement, trenching, refilling & testing of joints complete. (external work). - 50mm nominal OD pipes	m	497.12	Rupees Four Hundred Ninety Seven And Paise Twelve Only
13	360.00	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) with all lead and lift , loading and unloading and allother incidental charges etc., complete as per specification and direction of the engineer-in-charge of the work	Sqm	2537.05	Rupees Two Thousand Five Hundred Thirty Seven And Paise Five Only
14	42.00	Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 65mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	2420.00	Rupees Two Thousand Four Hundred Twenty Only
15	42.00	Supplying Installing, testing and commissioning of hydraulically operated sprinkler cabit Valve with water meter gong bell and trims as required, pressure gauges drain Valve, ball Valves check valve, strainer etc.-do-100 mm dia. Complete complete as per specifications.	Unit	821.63	Rupees Eight Hundred Twenty One And Paise Sixty Three Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	ntity	Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
16	5.00	Manufacturing,supply & fixing of Retro-Reflective Road name sign board Single Arrow size 1.6x0.9m size made out if wide angle cube corner micro prismatic grade sheeting confirming to IRC 67:2010 & type XI standards of ASTM D 4956-09 specifications and fixed over 2mm thick aluminium sheet back support frame of stainless steel supported by 30 NB 1.2 mm thick stainless steel pipe all around and 65 NB 1.5mm thick pipe vertical post (AISI 202 Grade) firmly fixed to the ground by means of properly designed foundation with M15 grade cement concrete 30cmx30cmx45cm etc. complete. The information message shall be made out of cut out letters in blue colour transparent overlay film as per IRC 67-2010 Guidelines, 7 years pre-qualification warranty for retro reflective sheeting from the original sheeting manufacturer and a certified copy of three years outdoor exposure report from an independent test lab for the product offerd shall be submitted by the contractor. The sign board shall be Retro-Reflective Type XI.	Each	15301.34	Rupees Fifteen Thousand Three Hundred One And Pais Thirty Four Only
17	10.00	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. (P.No. 112, I.No. 14.62 of PWD SR 2018-19)	Each	1417.71	Rupees One Thousand Four Hundred Seventeen And Paise Seventy One Only
18	1.00	Supply and Fixing of Pull Down Challenger. Metal: All tubular steel of 2 .5mm thickness are galvanized and zinc dipped. Joints are Robotic welded. All weld d joints are scalloped as necessary and welded to an approved MIG process.All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at II the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. Allmetal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for th e handles. Bearings:Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified internat ional certifying agency such as IPEMA,TUV,CPSC, or SGS only.The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates. Size_ L x W x H): 2570 x 805 x 2685 mm. Weight: 85.4 Kg Safety Area : 6287 x 4858 mm Capacity_2 Persons.	Each	260544.00	Rupees Two Lakh(s) Sixty Thousand Five Hundred Forty Four Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Quantity	Item Name	Unit	Rates quoted by Sri. T K SHANKARAPP MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
19	1.00	Supply and fixing of Seated Chest Press. Metal: All tubular steel of 2.Smm thikness are galvanized and z inc dipped. Joints are Robotic welded. All welded joints t1H • scalloped as necessary and welded to an approved MIG process. All welds an• 111 csed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w 11lt1ing points prior to finishing. All metal parts are powder coated using AKZO Nobel (11 ca t Wall powder to the thickness of 80-120 microns. All metal parts are tested in rn 1r a lt spray machine that uses a 5% NaCl solution in accordance to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handle!,,Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely Prt' ,ssembled equipment modules. Maintenance: Maintain according to EN 166630 and the maintenance guide. Safety: All products must be tested and certified to mt•(•lEN16630 safety standards with GS test mark. The EN 16630,certificates must be issued by a reputed notified international certifying agency such as IPEMA, 1UV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS inark as has been issued in the EN16630 safety certificates. All products must carry n GS mark :in it.. Size_ L x W x H): 1955 x 733 x 2058 mm. Weight : 86.6 Kg Safety Arc:.1: 5545 x 4470 mm Capacity_2 Persons.	Each	249688.00	Rupees Two Lakh(s Forty Nine Thousand Hundred Eighty Eigh Only
20	1.00	Supply and fixing of Self Weighted Rower. Metal: All tubular steel of 2.Smm thit.kness are galvaniied and zinc dipped. Joints are Robotic welded. All welded joiflts arc scalloped as necessary and welded to an approved MIG process. All welds arc dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our sa lt S'Pl,ray machine.that uses a 5% NaCl solution in accordance to IS07227 to speed up3 c_6rrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintain according to EN 16630 and the maintenance guide. Safety:All products must be tested and certified to meet EN16630 safety standards only by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS. The GS Mork• EN16630 Certificates must be in the name of tendering party and not any 3rd p;:11 ty All products must carry a GS mark on it.. Size_L x W x H}: 1390 x 805 x 1100 mm. Weight: 42.4 Kg Safety Area: 3790 x 3205 mm Capacity_1 Person.	Each	179124.00	Rupees One Lakh(s) Seventy Nine Thousar One Hundred Twenty Four Only

5/9/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
21	1.00	Supply and fixing of Elliptical Cross Trainer. Metal: All t\jbular steel of 2.Smm thickness are galvanized and zinc dipped. Joints are RClbotic welded. All weldecl 1oints a re scalloped as necessary and welded to an approve(j MIG process. All welds .i re dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at .ill the welding points prior to finishing. Alt metal parts are PCl\vder coated using AKZO Nobel Great Wall powder to the thickness of 80-120 microns. All metal parts are testecJ in our salt spray machine that uses a 5% NaCl solution iri ilccordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality €rip rubber is used for the handles. Bearings: Maintenance-free ball bearings. Scope of delivery: 1completely.pre-assembled equipment modules. Maintenance: Maintain according to EN 1G630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards w ith GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agl!ncy uch as IPEMA,TUV ,CPSC, or SGS only .The GS Mark-EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with 1 he tender document. Alt products must clearly display tt) GS mark as has been i ued in the EN16630 safety certificates. Size_L x W x H):126/ 582 x 1764 mm. Weight : 43.5 Kg Safety A rea: 4322 x 3632 mm Capacity 1Person.	Each	151984.00	Rupees One Lakh(s) Fifty One Thousand Nine Hundred Eighty Four Only
22	1.00	Supply and Fixing of Rider. Metal: All tubular steel of 2.smm thickness are galvd 1 ilzed and zinc dipped . Joints are Robotic welded. All weldect joints are scalloped as necessary and welded to an approved MIG proi;ess. .<\11 welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing.All metal parts are powder Clated using AKZO Nobel-G reat Wall powder to the thickness of 80-120 microns. All II\etal parts are tested in our sa lt spray machine that uses a 5% NaCl solution in accorcJ<ince to 1507227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubher is used for the handles. 5 Bearings : Maintenance-free ball bearings...Scope of c:l livery: 1completely pre-assembled equipment modules. Maintenance: Maint<1in according to EN 16630 a nd the maintenance guide. Safety: Alf products must b tested and certified to meet EN16630 safety standards with GS test mark. The El\! 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark-EN16630 Certificate must be in the name of tendering party and not any 3rd party. All products 'hust clearly display the GS mark as has been issued in the EN 16630 safety certificat . Size L x w x H): 910 x 655 x 1270 mm. Weight : 29.5 Kg Safety Area: 3310 x tnm C;pacity_l Person	Each	97704.00	Rupees Ninety Seven Thousand Seven Hundred Four Only

5/3/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
23	2.00	Supply and Fixing of Bicycle. Metal: All tubular steel of 25mm thickness are galvani zed and zinc dipped. Joints are Robotic welded. All welded joint s are S('.Illoped as necessary and w eldea to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the weltling points prior to finishing.All metal parts are powder coated using AKZO Nobel GreatWall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt v pray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up -orrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. each 1 125000 125000 131188 131188 134500 134500 Bearings: Maintenance-free ball bearings . Scope of delivery: 1completely pre assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to mee t EN16630 safety standards only by a reputed notified international certifying acency such as IPEMA,TUV,CPSC, or SGS. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Size_L x W x H): 1000 x 498 x 120 mm. Weight : 51.5 Kg Safety Area: 3400 x 3498 mm Capacity_ I Persons.	Each	135700.00	Rupees One Lakh(s) Thirty Five Thousand Seven Hundred Only
24	1.00	Supply and Fixing of Arm & Pedal Bike. Metal: All tubular steel of 2.Smm thickness a re galvanized and zinc dipped.Joints are Robotic welded.All welded joints are sca lloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles.Bearings : Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide.Safety : All products must be tested anEl certified to meet EN16630 safety standards only by a reputed notified international certifying agencv such as IPEMA,TUV, CPSC, or SGS. The GS Mark- EN16630 Certificates must be in t he name of tendering party and not any 3rd party.Size_L x W x H}: 830 x 500 x 1450 mm. Weight: 32 Kg Safety Area: 3830 x 2900 mm Capacity_ 1Persons.	Each	184552.00	Rupees One Lakh(s) Eighty Four Thousand Five Hundred Fifty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
25	1.00	Supply and Fixing of Tai Chi Spinners . Metal: All tubular steel of 2.Smm thicknp<.s are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sc;illoped as necessa ry and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the w eldin points prior to finishing. All metal parts are powder coated using AKZO Nobel G reat Wall powder to the thickness of 80- 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to JS07227 to speeu up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance - free ball bearings. Scope of delivery: 1completely pre-assembled equipment modules. Maintena nce:Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUY, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. Thecertificates must be attached with the tender document . All products must clearly -display the GS mark as has been issued in the EN15630 safety certificates. Size_ L x W x H): 1120 x 1150 x 1620 mm. Weight: 39 Kg Safety Area: 3520 x 3550 mm Capacity_3 Persons.	Each	124844.00	Rupees One Lakh(s) Twenty Four Thousand Eight Hundred Forty Four Only
26	1.00	Supply and fixing of Twist Stepper. Metal: All tubular steel of 2.Smrn thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sca lloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-GreatWall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark.The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV ,CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates . Size_ L x W x H): 1395 x 650 x1750 mm. Weight: 53.8 Kg Safety Area.: 3795 x 3050 mm Capacity_2 Persons.	Each	195408.00	Rupees One Lakh(s) Ninety Five Thousand Four Hundred Eight Only

17/3/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
27	1.00	Supply and fixing of HD Health Walker. Metal: All tubular steel of 2.Smm thickness are galvanized and zinc dipped. Joints are Robotic welded. All welded joint s arescalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our salt spray machine that uses a S% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Colour RAL 5019 Blue and RAL 1014 Beige Rubber: High quality grip rubber is used for the handles. Bearings: Maintenance-free ball bea rings.11 Scope of delivery: 1completely pre-assembled equipment modules. Maintenance: Maintain according to EQ_and the maintenance guide.Safety: All productsmust be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS oniy. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. The certificates must be attached with the tender document . All products must clearly display the GS mark as has been issued in the EN16630 safety certificates .Sizelx W xH): 1065 x 61S x 1364 mm.Weight: 51Kg. Safety Area: 4090 • 3555mm. Capacity 1 Person	Each	151984.00	Rupees One Lakh(s) Fifty One Thousand Nine Hundred Eighty Four Only
28	1.00	Supply and fixing of HD Squat Pushing. Metal All tub.ular steel of 2.Smm1hicknos are galvanized and zinc dipped. Joints are Robotic welded. All welded joints are sca lloped as necessary: and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing . All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns. All metal parts are tested in our sa lt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up corrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles 13 Bearings: Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules.Maintenance: Maintain according to EN 16630 andthe maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA, TUV, CPSC, or SGS only .The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party.All products must clearly display the GS ma rk as has been issued in the EN16630 safety certificates.Sizelx W x H): 2270 x 635 x 1640 mm. Weight: 60.2Kg.Safety Area: 5300 * 3685mm. Capacity 2 Persons	Each	233404.00	Rupees Two Lakh(s) Thirty Three Thousand Four Hundred Four Only

H.V. 5/2/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPP MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
29	1.00	Supply and fixing of HD Waist Twister. Metal : All tubular steel of 2.Smm thic k11ess are ga:vanized and zinc dipped. Joints are Robotic welded. All welded joints are scJlloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges and burrs. Zinc Primer Paint is applied at all the welding points prior to finishing. All metal parts are powder coated using AKZO Nobel-Great Wall powder to the thickness of 80-120 microns.Al l metal parts are tested in our salt spray machine that uses a 5% NaCl solution in accordance to IS07227 to speed up rrosion for 3000 hrs. Rubber: High quality grip rubber is used for the handles. arings : Maintenance-free ball bearings.Scope of delivery: 1completely pre-assembled equipment modules. Maintenance : Maintain according to EN 16630 and the maintenance guide. Safety: All products must be tested and certified to meet EN16630 safety standards with GS test mark. The EN 16630 certificates must be issued by a reputed notified international certifying agency such as IPEMA,TUV, CPSC, or SGS only. The GS Mark- EN16630 Certificates must be in the name of tendering party and not any 3rd party. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. Size_L x W x H}:1460 x 1310 x USO mm. Weight: 39.l Kg Safety Area : 4360 x 4510 mm Capacity_3 Persons.	Each	141128.00	Rupees One Lakh(s) Forty One Thousand One Hundred Twenty Eight Only
30	1.00	Providing ,fabricating and fixing Special Multiplay Systems consists of FRP moulded with Aluminium chequered platforms of size 5x5 ft with 4 support piller made out of 75 mm dia G.I "B"pipes fixed in cement concrete 1:2:4.The patforms are to be covered with pyramid shaped FRP roof. The platform is to be with tubular slide & Mini Aquva tunnel Slide made up of high quality FRP the slide is to fixed at a height of 11ft and runs for a length of not less than twenty ft and the slide should be supported at regular intervals of 6ft using M.S pipes support and the platform ladder with 25mm dia MS pipes with suitable hand rails and steps made out of G I sheet with tred 4" with powder coated finish,fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-corrossive ,fade free,tough grade,durable hard and should prevent uv light.The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift,loading and unloading and any incidental charge required for it	Each	645932.00	Rupees Six Lakh(s) Forty Five Thousand Nine Hundred Thirty Two Only
31	1.00	Providing,fabricating and fixing of spiral climber of height not less than 10ft made out of 25mm dia MS pipe with Aluminium chequered plate platform of size 3x3 ft with 4 legs made out of 75mm dia G.I pipe fixed cement concrete 1:2:4. The platforms are to be covered with pyramid shaped FRP roof .The platform is to be fitted with single lane slide made up of high quality FRP the slide is fixed at a height of 9 ft and runs for a length of not less than 20ft the slide should be supported at regular interval of 4 ft using M.S pipes support powder coated,fine quality FRP with suitable design and as per drawing platforms should be placed at approximately 9 ft from ground level. Moulded FRP slides are non-corrossive,fade free,tough grade,durable hard and should prevent UV light. The work should be executed as per the standard specification and directions of the engineer in charge of the all lead and lift, loading and un loading and any incidental charges required for the successful completion of the work (ALL FRP items are gel water finish or stoving paint in ovens)	Each	195408.00	Rupees One Lakh(s) Ninety Five Thousand Four Hundred Eight Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
32	1.00	Providing fabricating and fixing Multiplay Special slider systems consisting of the plat form with 25mm dia MS pipe and Aluminium chequered plates of size 3x3 ft fitted at 7 ft height from ground level with 4 legs made out of 65mm dia G.I pipes fixed cement concrete 1:2:4. The plat forms is to be fitted with FRP wave slide spiral slide and standard slide with vertical ladder on one side each with GI sheet steps of treads 4" 25mm dia MS pipes with suitable Hand rails fixed at a height of 5 ft and runs for a length of not less than 12 ft the platforms are to be coverd with ryramid Shape FRP roof this slide should be supported at regular intervals of 4 ft using MS pipes support powder coated fine quality FRP with suitable design and as per drawing Moulded FRP slides are non-Corrossive fade free ,tough grade ,durable hard and should prevent uv light.The work should be executed as per the standard specifications and directions of the engineer in charge with all lead and lift,loading and unloading and any incidental charges required for the successful competion of the work (ALL FRP items are gel water finish or stoving paint in ovens)	Each	564512.00	Rupees Five Lakh(s) Sixty Four Thousand Five Hundred Twelve Only
33	1.00	Providing and fixing childern play bridge with MS perforated tunnel and wave bridge and Arch bridge and hanging bridge made out of MS pipe and chequred plates uns for a height 11 ft to 5 ft the work should be executed as per the standard specification and direction of the engineer in charge of the with all lead and lift ,loading and unloading and any incidenteial charges required for the successful competion of work (all swings chains are rubber coated &all 'S' hooks are stainless steel)	Each	130272.00	Rupees One Lakh(s) Thirty Thousand Two Hundred Seventy Two Only
34	1.00	10HP /7.5KW Submersible Three Phase Pumps ATLANTA, SUGUNA, CRI, KIRLOSKAR and other equivalent Pumps	Each	51951.39	Rupees Fifty One Thousand Nine Hundred
35	120.00	Providing, fitting and fixing mild steel railing complete as per drawing and Technical Specification complete as per specifications	Rmtr	3035.64	Rupees Three Thousand Thirty Five And Paise Sixty Four
36	20.00	Providing and fixing Cement Concrete Benches with Base, Back rest and Pedestals of size, Shape and Design including Transportation and with lead and lift, loading and unloading, Earthwork excavation and fixing in 1:4:8 (wherever necessary) and curing etc., complete as per standard Specification and direction of engineer in charge.	Nos	11409.66	Rupees Eleven Thousand Four Hundred Nine And Paise Sixty Six Only
37	4.86	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in hard soil, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.	Cum	606.35	Rupees Six Hundred Six And Paise Thirty Five Only
38	0.61	Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	5871.06	Rupees Five Thousand Eight Hundred Seventy One And Paise Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAPPA (MESPC INFRA PROJECTS PRIVATE LIMITED)	
				In figures	In words
	3.34	Providing and laying in position reinforced cement concrete of Design Mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.460 cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters, columnspillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.	Cum	6512.02	Rupees Six Thousand Five Hundred Twelve And Paise Two Only
40	30.00	Fabricating, supplying and erection of ...Mtrs long hot dip Galvanized Conical pole with BSEN 10025 grade S 355 JO steel plate for shaft, IS 2062 for base plate with door opening arrangements, including suitable boards, Bakelite sheet and MCBs as per IS specifications suitable to withstand the wind speed of 47 m/sec for .....Mtrs pole in single section and single joint welded as per IS 9595/IS 10178AWS having dimensions bottom .....mm, top....mm with 3mm thick, suitable base plate and 4Nos of ..... long J bolts along with template and the pole shall be hot dip galvanized in single dipping with not less than 65micron as per ASTM-A123 and 153 etc.,(excluding foundation) as per drawing appended. 7 meters - Top 75mm and bottom 145 mm dia	Each	15241.82	Rupees Fifteen Thousand Two Hundred Forty One And Paise Eighty Two Only
41	1390.00	Supplying of 1.1 KV class UG cable in having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class	Per Mtr	128.97	Rupees One Hundred Twenty Eight And Paise Ninety Seven Only
42	1390.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete	Per Mtr	92.28	Rupees Ninety Two And Paise Twenty Eight Only
43	1390.00	Labour charges for laying of UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct.	Per Mtr	11.72	Rupees Eleven And Paise Seventy Two Only
44	30.00	Supplying and fixing of heavy duty cable glands suitable or UG cable o 1.1KV class (metal only)	Each	93.36	Rupees Ninety Three And Paise Thirty Six Only
45	30.00	Supplying tinnd copper lugs and crimping and wiring to terminal point for wire of the following sizes	Each	8.30	Rupees Eight And Paise Thirty Only
46	30.00	Supplying, and fixing of Hot dip Galvanized M.S.Bracket suitable for out door luminaries and mounted on Octagonal pole using necessary bolts, nuts etc., complete.Single Arm Bracket with 1500mm Standard 40/50MM dia	Each	2605.44	Rupees Two Thousand Six Hundred Five And Paise Forty Four Only

5/3/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Rates quoted by Sri. T K SHANKARAP MESPC INFRA PROJECTS PRIVATI LIMITED)	
				In figures	In words
47	30.00	LED Street light. Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs. 50000 hr. @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4 KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application.)Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools. 2)110 Watts	Each	37170.94	Rupees Thirty Seve Thousand One Hundr Seventy And Paise Ninety Four Only
48	6.00	Supply, installtion, testing and commissioning of STREET LIGHT PANEL made up of 16SWG CRCA sheet for body and 14 SWG CRCA sheet for door, outdoor type, floor mounting, powder coated,Degree of projection IP56, with necessary hard ware, interconnection wiring & accessories complete comprising of the following Incomming : 63A 4P 10KA MCB + 2 nos. 32A 3P AC1 contactor + 2 nos. 24hrs Timer Outgoings :18 Nos 20A 10KA SP MCB	Each	4885.20	Rupees Four Thousan Eight Hundred Eighty Five And Paise Twenty Only
49		GST @ 12%			

Contractor

Executive Engineer
Project Division
Yelahanka Zone